

Overview of the (Provisionally Named) Sodegaura Thermal Power Station New Units 1–3 Construction Plan

1. Plan Name (Provisional)
Sodegaura Thermal Power Station New Units 1–3 Construction Plan
2. Location:
2-1 Nakasode, Sodegaura city, Chiba
3. Plan Overview:

	Existing Facilities (Current Situation)	After Replacement*
Generation Method	Steam (Units 1–4)	Gas Turbine Combined Cycle (New Units 1–3)
Max. Output	Unit 1: 600 MW Unit 2: 1,000 MW Unit 3: 1,000 MW Unit 4: 1,000 MW Total: 3,600 MW	New Unit 1: Approx. 870 MW New Unit 2: Approx. 870 MW New Unit 3: Approx. 870 MW Total: Approx: 2,610 MW
Fuel	LNG	LNG
Start of Operation	Unit 1: Aug. 1974 (Decommissioned Sep. 2025) Unit 2: Sep. 1975 Unit 3: Feb. 1977 Unit 4: Aug. 1979	New Unit 1: 2032 (planned) New Unit 2: 2033 (planned) New Unit 3: 2041 (planned)

*Replacement plans may change going forward.

END